# bartec

# CH4 65 L - 2.3 cubic feet

CH41 White Frame Clear Glass Door



CH41 No-Top Version



CH41 No-Top Version



CH41 Opaque Black Glass Door





Available as Automatic, Semi-Automatic and Upgradeable

## **Product**

**Door Type** 

**Dimensions** 

**Optional** 

41 Sensors, 31 Product Types Also Available with Big Bottle Balcony

Foam-Core Door Panel

Wood Door

Glass Door: Clear, Opaque, or

with your Logo

W: 17.72 in - 450 mm

H: 25.59 in - 650 mm

D: 19 in - 480 mm with compressor

D: 17.5 in - 445 mm with absorption

3 balcony (optional) Integrated Dry Sections

**External Sections for Dry Products** 

## **Technical**

# **Specifications**

## Standard CH41

Shelves with Sensors

20 bottles

5 bottles (laid down) can be replaced by guest convenience

shelf

Adjustable shelves (no tools needed)

**Door Balconies** with Sensors

2 x 8 miniatures/

snacks

Big bottle available

Server OS

SQL 2012 R2 and Up

Software

Web-based Windows

Interface Types

TCP IP/RS 232

Available for all PMS

Data

Communication

Ethernet Twisted Pair ZigBee (wireless)

Wi-Fi (wireless)

**Database** 

**Engine** 

Microsoft SQL Server 2012 and

Up

Cooling Unit

Compressor Absorption

Sensors


Infrared Microswitches

Magnetic

Voltage

110-240 VAC /

50-60 HZ



Integrated dry sections available with wooden door versions

### 38 inch<sup>2</sup> / 240 cm<sup>2</sup> clear area for airflow

The minibar must be properly ventilated. A channel for air circulation under the minibar, passing up and over the cooling unit and exhausting out from the minibar is mandatory. A 50 mm free space is recommended between the wall or cabinet back and cooling unit.

